

PORT OF HOOD RIVER

BID SHEET - Lower Hanel Mill Access Road and Grading Project

Addendum #3- Issued 8-19-19

Bid Number	Specificat	Item Description	Unit	Quantity	Unit Cost	Bid Item Total
19-025-1	00210	Mobilization	Subtotal			
19-025-1.1	00210	Contractor Mobilization	LS	1		
19-025-2	00280	Erosion Control	Subtotal			
19-025-2.1	00280.16	Furnish and Place Silt Fence	LF	1,562		
19-025-2.2	00280.16	Furnish and Place Strawbale Barrier	EACH	5		
19-025-2.3	00280.16	Furnish and Place Construction Entrance	EACH	1		
19-025-4	00320	Excavation and Grading	Subtotal			
19-025-4.1	00330	General Excavation	CY	16,350		
19-025-4.2	00330	Imported Structural Fill- Wetland (1.5-0 Material)	CY	3,840		
19-025-4.3	00330	Imported Structural Fill- General Grading (1.5-0 Material)	CY	3,450		
19-025-4.4	00350	Furnish and Place- Geotextile- Wetland Stabilization	SF	37,500		
19-025-4.5	00390	Furnish and Place - Rip-Rap	SF	720		
19-025-4.6	00330, 003	Construct Finish Grade on Drainage Ditch	LF	1,000		
19-025-4.7	00330	Roadway Construction	Subtotal			
19-025-5	00610	Scarification and Excavation of Existing Roadway	SY	1,761		
19-025-5.1	00350	Furnish and Place - Geotextile	SF	16,900		
19-025-5.2	00641	Furnish and Place- 4"-1.5" Minus Base Rock	CY	200		
19-025-5.3	00641	Furnish and Place- 2"-3/4" Levelling Coarse Rock	CY	100		
19-025-5.4	00744	Furnish and Place- 3" HMAc	TON	305		
19-025-5.5	00867	Furnish and Place- Stop Bar	EACH	1		
19-025-5.5	00940	Furnish and Place- Stop Sign	EACH	1		
19-025-6		Stormwater	Subtotal			
19-025-6.1	00415	Furnish and Place Ditch Inlet, Type D	Each	2		
19-025-6.2	00445	Furnish and Place MP 12" Storm Drainage Pipe	LF	120		
19-025-7		Sanitary Sewer	Subtotal			
19-025-7.1	00415	Extend Sanitary Cleanout	LS	2		
19-025-8	01030	Seeding	Subtotal			
19-025-8.1	01030	Furnish and Plant- Permanent Seeding	Acre	5		
					Total	