



1000 E. Port Marina Drive • Hood River, OR 97031 • (541) 386-1645 • Fax: (541) 386-1395 •  
[www.portofhoodriver.com](http://www.portofhoodriver.com) • Email: porthr@gorge.net

**Stadleman Waterline**

Clarification #2- Issued: April 23, 2018

---

The following questions were asked on 4/13/2018:

1. The contract time does not allow enough time for the PRV vault assembly material to be delivered to the project. These vault assemblies are taking 8-10 weeks for delivered to the job. Is there going to be additional time added to the project to allow for the PRV material:

A1. Yes. The contract time has been extended to a final completion date of July 27, 2018. The bid due date has also been extended to Friday, April 27 at 3:00 PM. Working days have increased from 34 to 50 working days.

2. The plans show that Crystal Springs will have the 10" valves installed before we start the project. Yet in the bid proposal there are two 10" valves included for this project. Are we to install these valves for the project?

A2. Crystal Springs water District(CSWD) has a gate valve already installed at "Connection B". The Contractor will need to flush the system per the specifications and coordinate with CSWD for this connection. "Connection A" has not yet been installed by CSWD. The Contractor will need to terminate the pipe with a blow off valve for a later connection by CSWD.

3. Are we to assume that all pressure and chlorination testing will be done before Crystal Springs does their water services on the new line.

A3. Yes.

4. There is a relief valve on the bid tab but the plans do not show that assembly on the plans.

A4. The relief valve was made larger in the revised plan set.

Port of Hood River  
*economic future.*

*Providing for the region's*

**An addendum will be issued on Monday, April 23, 2018 that will address these clarifications and additional changes that have been made to the contract documents, plans and specifications.**