

Item	Description	Unit	Qty.	Unit Cost	Total
1	Mobilization (00210)	LS	ALL		
2	Temporary Work Zone Traffic Control, Complete (00225)	LS	ALL		
3	Erosion Control (00280)	LS	ALL		
4	Pollution Control Plan (00290)	LS	ALL		
5	Construction Survey Work (00305)	LS	ALL		
6	Removal of Structures and Obstructions (00310)	LS	ALL		
7	Clearing and Grubbing (00320)	LS	ALL		
8	Import Embankment Material (00330)	CY	7,500		
9	Embankment in Place (00330)	CY	22,900		
10	Wetland Mitigation Pond Excavation (00330)	CY	10,500		
11	12 Inch Subgrade Stabilization (00331)	SY	1,000		
12	Rip Rap Geotextile, Type 1 (00350)	SY	140		
13	Subgrade Reinforcement Geogrid (00350)	SY	19,930		
14	Loose Riprap, Class 50 (00390)	CY	30		
15	Loose Riprap, Class 100 (00390)	CY	20		
16	2 Inch Pressure Sewer Pipe (00445)	FT	1,590		
17	4 Inch Sanitary Sewer Pipe (00445)	FT	140		
18	6 Inch Sanitary Sewer Pipe (00445)	FT	650		
19	6 Inch Storm Sewer Pipe (00445)	FT	80		
20	8 Inch Storm Sewer Pipe (00445)	FT	1,440		
21	12 Inch Storm Sewer Pipe (00445)	FT	350		
22	15 Inch Storm Sewer Pipe (00445)	FT	200		
23	18 Inch Storm Sewer Pipe (00445)	FT	445		
24	24 Inch Storm Sewer Pipe (00445)	FT	190		
25	Concrete Sanitary Sewer Manholes (00470)	EA	1		
26	Concrete Storm Sewer Manholes (00470)	EA	6		
27	Concrete Manholes, Shallow With Pressure Sanitary Sewer Drop Connection (00470)	EA	1		
28	Concrete Manholes, Storm Sewer Pollution Control (00470)	EA	1		
29	Concrete Inlets, Type G-2 (00470)	EA	5		
30	Concrete Inlets, Ditch Inlet Type D (00470)	EA	1		
31	Cleanout (00470)	EA	18		
32	Pond Outlet Structure (00470)	EA	1		
33	Sanitary Sewer Step System (00485)	LS	1		
34	Aggregate Base (00640)	CY	4,230		
35	Aggregate Base - Recycled (00640)	CY	3,820		
36	Aggregate Drain Rock (00640)	CY	300		
37	Level 4, 1/2 inch ACP (00745)	Ton	2,860		
38	Concrete Curbs, Standard Curb (00759)	LF	690		
39	Bollards (00815)	EA	3		

40	Storm Sewer, Sanitary Sewer, and Water Lateral Marker (00842)	EA	14		
41	Longitudinal Pavement Markings - Paint (00860)	LF	1370		
42	Pavement Legend, Type AB: Disabled Parking (00867)	EA	2		
43	Pavement Legend, Type AB: Arrows (00867)	EA	2		
44	Pavement Bar, Type AB (00867)	SF	19		
45	Signs, Standard Sheeting, Sheet Aluminum (00940)	LS	ALL		
46	Electrical Systems (00960)	LS	ALL		
47	Permanent Seeding, Mix No. 2 (01030)	Acres	1.5		
48	Swale/Pond Permanent Seeding (01030)	Acres	0.5		
49	Chain Link Fence (01050)	FT	45		
50	Farmer's Irrigation District Irrigation System (01140)	LS	1		
51	2 Inch Irrigation Line (01140)	LF	700		
52	8 Inch Ductile Iron Water Pipe (01140)	LF	940		
53	12 Inch Ductile Iron Water Pipe (01140)	LF	1340		
54	8 Inch Gate Valve (01150)	EA	1		
55	12 Inch Gate Valve (01150)	EA	8		
56	1 Inch Combination Air Release / Air Vacuum Valve Assembly (01150)	EA	1		
57	Hydrant Assemblies (01160)	EA	2		
Total Bid Schedule A:					

BID SCHEDULE B – ADDITIVE ALTERNATE 1

Item	Description	Unit	Qty.	Unit Cost	Total
58	Fueling Pad (00756)	LS	1		
59	New Aircraft Fueling System (00950)	LS	ALL		
Total Bid Schedule B:					
Written Bid Total = Bid Schedule A + Bid Schedule B:					

Contractor Name	
Address	
Address	
City, State, Zip	
Phone	
Fax	
Email	
Registration Number	
Contact	
Phone	