



Port of  
Hood River

*Providing for the region's economic future.*

**INDUSTRIAL/COMMERCIAL FACILITIES • AIRPORT • INTERSTATE BRIDGE • MARINA**

1000 E. Port Marina Drive • Hood River, OR 97031 • (541) 386-1645 • Fax: (541) 386-1395 • [www.portofhoodriver.com](http://www.portofhoodriver.com) • Email: [porthr@gorge.net](mailto:porthr@gorge.net)

## **North Apron Rehabilitation Project - Ken Jernstedt Airfield Clarification No. 1**

---

**Issued: Friday, March 20, 2020**

**See questions and answers asked by potential bidders:**

Q1. Can rap be used in the AC mix design? If so, what percentage?

**A1. No, rap is not allowed in the AC mix.**

Q2. What is the tolerance for the rough grading for the wetland that will be done by others?

**A2. Subgrade tolerance is ¾" per the section below.**

**00330.70 General - Immediately before completing the earthwork:**

- **Blend the tops of cutbanks with the adjacent terrain.**
- **Trim and finish all Roadbeds, ditches, waterway channels, and other excavations and embankments to the lines, grades, and Cross Sections established.**
- **Clean up debris and foreign matter of all kinds on the entire Right-of-Way area. Dispose of materials as directed.**
- **Finish the Subgrade to be within a tolerance of plus or minus 0.06 foot from the established line, grade, and Cross Section and to be free of ruts, depressions and irregularities.**
- **In planting and seeding areas, remove all rocks, Boulders, and vegetative matter.**
- **Remove all litter, debris and obstructions.**

Q3. Will there be any material from the adjacent job that the Contractor will have to haul or touch?

**Q3. No. The project scopes are separate with no cross over in touching materials. Each Contractor will be responsible for their materials, grading and hauling.**